


GUARDRAIL SCHEDULE				
NO.	ITEM DESCRIPTION / TYPE	BEGIN STA.	OFFSET	LENGTH
1	GR END TREATMENT ATTENUATOR, TYPE 1	11+12.00	15.75	50.00
2	STEEL BEAM GUARDRAIL	11+69.50	14.50	12.50
3	GR TO BARRIER CONNECTION, TYPE 2	11+82.32	13.75	27.00
4	GUARDRAIL END TREATMENT, TYPE 4-27	11+66.77	-18.10	25.00
5	GR TO BARRIER CONNECTION, TYPE 2	11+89.83	-13.75	27.00
6	GR TO BARRIER CONNECTION, TYPE 2	12+25.80	13.75	27.00
7	GR END TREATMENT ATTENUATOR, TYPE 1	12+49.12	14.62	50.00
8	GR TO BARRIER CONNECTION, TYPE 2	12+33.50	13.75	27.00
9	GR END TREATMENT ATTENUATOR, TYPE 1	12+58.90	13.75	50.00

NOTE: INSTALL GR #6 AND #7 TANGENT TO THE BRIDGE PARAPET. FLARE AT END OF ATTENUATOR ACHIEVED FROM THE CURVATURE OF THE ROADWAY.

CURB SCHEDULE		
NO.	ITEM DESCRIPTION / TYPE	LENGTH
1	PCC CURB TYPE 1-4	21.00



Y:\SUSSEX\225\BRIDGE\T201107303\PLANS\GP01.DGN